

USE OF AUS-SPEC PUBLICATIONS

1. Greater Taree City Council grants a non-exclusive Licence to the end user for the use of Greater Taree City Council AUS-SPEC Specifications and hereafter referred to as "AUS-SPEC".
2. AUS-SPEC will only be used for works where Greater Taree City Council is a Consent Authority for, or owner or operator or manager of, assets, or consultant to same.
3. No copying or modification of AUS-SPEC documents is permitted unless authorised by Greater Taree City Council in writing.
4. The end user shall be responsible for the correct application of AUS-SPEC. The end user acknowledges that Standards Australia, IPWEA and Greater Taree City Council have no control over and cannot influence the circumstances in which AUS-SPEC may be used by the end user and, accordingly, the end user agrees to indemnify and hold harmless Standards Australia, IPWEA and Greater Taree City Council against all actions, suits, proceedings, claims, demands, costs or losses whatsoever which may be brought, commenced or made against them, either jointly or separately, or which may be suffered by them or any of them in respect of the use of AUS-SPEC.
5. This License is personal and shall not be assigned, and the end user shall not allow any other person to use or have access to AUS-SPEC.
6. This Agreement shall be governed and construed in accordance with the laws of New South Wales.
7. These Licence conditions are deemed to have been accepted by the end user.



DEVELOPMENT
CONSTRUCTION
SPECIFICATION

C211

CONTROL OF EROSION AND
SEDIMENTATION

Amendment Record for this Specification Part

This Specification is Council's edition of the AUS-SPEC generic specification part and includes Council's primary amendments.

Details are provided below outlining the clauses amended from the Council edition of this AUS-SPEC Specification Part. The clause numbering and context of each clause are preserved. New clauses are added towards the rear of the specification part as special requirements clauses. Project specific additional script is shown in the specification as italic font.

The amendment code indicated below is 'A' for additional script 'M' for modification to script and 'O' for omission of script. An additional code 'P' is included when the amendment is project specific.

Amendment Sequence No.	Key Topic addressed in amendment	Clause No.	Amendment Code	Author Initials	Amendment Date
1	Reference Documents (a) Erosion and Sediment Control Policy	C211.02	A	JM	19/2/99
2	Reference Documents (c) Department of Housing – Managing Urban Stormwater - Soil and Construction Manual 1998	C211.02	A	JM	19/2/99
3	Erosion and Sediment Control Plan 4 added "Managing Urban Stormwater – Soil and Construction Manual 1998"	C211.03	A	JM	19/2/99
4	Measure and Payment Clause "Pay Items" omitted	C211.20	O	JM	19/2/99

SPECIFICATION C211 CONTROL OF EROSION AND SEDIMENTATION

GENERAL

C211.01 SCOPE

1. The work to be executed under this Specification consists of the construction of structures and the implementation of measures to control erosion and sedimentation. These may be temporary or permanent.
2. The Contractor shall plan and carry out the whole of the Works to avoid erosion and sedimentation of the site, surrounding country, watercourses, waterbodies and wetlands.

C211.02 REFERENCE DOCUMENTS

1. Documents referenced in this specification are listed in full below whilst being cited in the text in the abbreviated form or code indicated.

**Documents
Standards
Test Methods**

(a) Council Specifications

- C212 - Clearing and Grubbing
- C213 - Earthworks
- C273 - Landscaping
- Erosion and Sediment Control Policy

(b) State Legislation

NSW Clean Waters Act, 1970
Soil Conservation Act, 1938
Water Act, 1912

(c) Other

NSW Department of Land and Water Conservation (DLWC)
Urban Erosion and Sediment Control
Department of Housing – “Managing Urban Stormwater – Soil and Construction
Manual 1998”

C211.03 EROSION AND SEDIMENTATION CONTROL PLAN

1. For consideration of erosion and sedimentation control measures, the site shall be divided into sections based on the catchment area draining to each permanent drainage structure in the works. In addition to the area bounded by the road reserve, the sections shall include:

Site Sections

- (a) access and haulage tracks,
- (b) borrow pits and
- (c) compound areas, such as Contractor's facilities and concrete batching areas.

2. At least fourteen days before the natural surface is disturbed on each of these sections, the Contractor shall submit to Council an Erosion and Sedimentation Control Plan for that section. This Plan shall be superimposed on half-sized drainage drawings of the works and shall be detailed for each catchment area of the works.

Section Plan

3. The Plan shall consist of scale diagrams indicating:

Plan Inclusions

- (a) features of the site including contours and drainage paths,
- (b) relevant construction details of all erosion and sedimentation control structures,
- (c) all permanent and temporary erosion and sedimentation control measures, including the control measures to be implemented in advance of, or in conjunction with, clearing and grubbing operations as required under the Specification for CLEARING AND GRUBBING,
- (d) an order of works based upon construction and stabilisation of all culverts and surface drainage works at the earliest practical stage, and
- (e) proposed time schedules for construction of structures and implementation of measures to control erosion and sedimentation.

4. The DLWC publication Urban Erosion and Sediment Control and Department of Housing "Managing Urban Stormwater – Soil and Construction" manual 1998 provides guidance on typical permanent and temporary erosion and sedimentation control measures which may be required and guidance in the preparation of an Erosion and Sedimentation Control Plan.

Guidance

5. No work shall commence until Council has approved the Erosion and Sedimentation Control Plan. Such approval shall not relieve the Contractor of the full responsibility to provide whatever measures are required for effective erosion and sedimentation control at all times.

Contractor's Responsibility

6. The Contractor shall adhere to the approved Erosion and Sedimentation Control Plan. The Contractor shall submit a revised Erosion and Sedimentation Control Plan for approval by Council fourteen days in advance of intended variation from the approved plan.

Adherence to Plan

C211.04 EROSION AND SEDIMENTATION CONTROL MEASURES

1. Erosion and sedimentation control measures shall include, but shall not be limited to, the following:

Scope

- (a) The installation of permanent drainage structures before the removal of topsoil and commencement of earthworks for formation within the catchment area of each structure.
- (b) The prompt completion of all permanent and temporary drainage works, once commenced, to minimise the period of exposure of disturbed areas.
- (c) The stabilisation of diversion and catch drains to divert uncontaminated runoff from outside the site, clear of the site. Catch drains shall be installed and lined, as specified or as directed by the Superintendent, before the adjacent ground is disturbed and the excavation is commenced.
- (d) The passage of uncontaminated water through the site without mixing with contaminated runoff from the site.
- (e) The provision of contour and diversion drains across exposed areas before, during and immediately after clearing and the re-establishment

and maintenance of these drains during soil removal and earthworks operations.

- (f) The provision of sediment filtering or sediment traps, in advance of and in conjunction with earthworks operations, to prevent contaminated water leaving the site.
- (g) The restoration of the above drainage and sedimentation control works on a day to day basis to ensure that no disturbed area is left without adequate means of containment and treatment of contaminated water.
- (h) The limitation of areas of erodible material exposed at any time to those areas being actively worked.
- (i) The minimisation of sediment loss during construction of embankments by means such as temporary or reverse superelevations during fill placement, constructing berms along the edge of the formation leading to temporary batter flumes and short term sediment traps.
- (j) The progressive vegetation of the site, in accordance with the Specification for LANDSCAPING, as work proceeds.

PERMANENT EROSION AND SEDIMENTATION CONTROL

C211.05 EARTHWORKS FOR PERMANENT EROSION AND SEDIMENTATION CONTROL BASINS

1. Earthworks for permanent erosion and sedimentation control basins shall be constructed to the planned levels and dimensions shown on the Drawings or such levels and dimensions as determined by the Superintendent. **Planned Levels**
2. The entire storage and embankment foundation area of permanent erosion and sedimentation control basins shall be cleared in accordance with the Specification for CLEARING AND GRUBBING and shall be stripped of topsoil and any unsuitable material under embankments removed in accordance with the Specification for EARTHWORKS. **Site Preparation**
3. The embankments shall be constructed in accordance with the Specification for EARTHWORKS. **Compaction Requirements**
4. If payment for embankment construction is on a Schedule of Rates basis, at least three days before construction of the embankment the Contractor shall provide the Superintendent with survey information which will be sufficient to subsequently measure the volume of the constructed embankment. **Contractor to Provide Survey Information**

C211.06 INLETS, SPILLWAYS AND LOW FLOW OUTLETS FOR SEDIMENTATION CONTROL BASINS AND SEDIMENT TRAPS

1. Inlets and spillways shall be constructed using rock filled woven galvanised steel mattresses laid on a needle punched, mechanically bonded, non-woven geotextile filter fabric, as shown on the Drawings or as directed by the Superintendent. The rock filled mattresses shall be laid in accordance with the manufacturer's instructions and Specification. **Rock Mattresses**
2. A low flow outlet consisting of a 150 mm diameter plastic pipe shall be installed as shown in the Drawings. No extra payment shall be made for this work which shall be regarded as part of the construction of the sedimentation control basin. **Plastic Pipe Outlet**

C211.07 DROP INLET SEDIMENT CONTROL

1. Drop inlet sediment traps and inlet control banks shall be constructed on completion of each gully pit unless otherwise directed by the Superintendent. These drop inlet sediment traps and inlet control banks are additional to the temporary sedimentation control measures that may be required under Clause C211.10 during construction of the gully pits.

Time of Construction

2. The drop inlet sediment traps are intended to remove sediment from the surface flow before it enters the drainage system. The inlet control banks shall be constructed as required to prevent the surface flows bypassing the gully pits.

Purpose

3. The drop inlet sediment traps shall be constructed as shown on the Drawings. The associated inlet control banks shall consist of at least two courses of sandbags containing a 10:1 sand/cement mix. The bags shall be keyed at least 25 mm into the surface, dampened sufficiently to ensure hydration of the cement and tamped lightly to provide mechanical interlock between adjacent bags.

Control Banks

C211.08 CLEANING SEDIMENTATION CONTROL STRUCTURES

1. The Contractor shall clean out permanent sedimentation control structures, cleaning out whenever the accumulated sediment has reduced the capacity of the structure by 50 per cent or more, or whenever the sediment has built up to a point where it is less than 300 mm below the spillway crest. All permanent sedimentation control structures shall be cleaned out by the Contractor prior to Practical Completion of the Works.

Contractor's Responsibility

2. Accumulated sediment shall be removed from permanent sedimentation control structures in such a manner as not to damage the structures. The sediment removed shall be disposed of in such locations that the sediment will not be conveyed back into the construction areas or into watercourses. The Contractor shall provide and maintain suitable access to permanent sedimentation control structures to allow cleaning out in all weather conditions.

Removal of Sediment

C211.09 RESERVED

(For additional Site Specific Permanent Control Measures.)

TEMPORARY EROSION AND SEDIMENTATION CONTROL

C211.10 GENERAL

1. The Contractor shall ensure that effective erosion and sedimentation control is provided at all times during the Contract.

Contractor's Responsibility

2. Runoff from all areas where the natural surface is disturbed by construction, including access roads, depot and stockpile sites, shall be free of pollutants as defined in the Clean Waters Act 1970 before it is either dispersed to stable areas or directed to natural watercourses. The Contractor shall be responsible for all temporary erosion and sedimentation control measures required for this purpose.

Pollutant Free

3. The Contractor shall provide and maintain slopes, crowns and drains on all excavations and embankments to ensure satisfactory drainage at all times. Water shall not be allowed to pond on the works unless such ponding is part of an approved Erosion and Sedimentation Control Plan.

Maintenance by Contractor

C211.11 TEMPORARY DRAINS

1. Runoff from areas exposed during the work shall be controlled by construction of temporary contour drains and/or temporary diversion drains. Generally, a temporary contour drain or temporary diversion drain takes the form of a channel constructed across a slope with a ridge on its lower side. They may require progressive implementation and frequent alteration as the work progresses.

***Control of
Runoff***

2. Contour drains, which follow points on the natural surface of approximately the same elevation, shall be provided immediately after a construction site is cleared to intercept and divert runoff from the site to nearby stable areas at non-erosive velocities. Contour drains shall be formed with a grade of neither less than 1 per cent nor more than 1.5 per cent and shall be spaced at intervals of neither less than 20 m nor more than 50 m, depending on the erodibility of the exposed soil. Contour drains shall be constructed as shown on the Drawings.

***Contour
Drains***

3. Diversion drains shall be provided across haul roads and access tracks when such roads and access tracks are identified as constituting an erosion hazard due to their steepness, soil erodibility or potential for concentrating runoff flow. Diversion drains shall be formed to intercept and divert runoff from the road or track to stable outlets. Spacing of diversion drains shall not be greater than that required to maintain runoff at non-erosive velocities.

***Diversion
Drains*****C211.12 TEMPORARY SEDIMENT TRAPS**

1. Temporary sediment-trapping devices shall be provided during construction to remove sediment from sediment-laden runoff flowing from areas of 0.5 hectares or more before the runoff enters natural watercourses or adjacent land.

***Sediment
Traps*****C211.13 BATTER PROTECTION**

1. The Contractor shall take all necessary action to protect batters from erosion during the Contract.

***Contractor's
Responsibility***

2. Scour of newly-formed fill batters during and after embankment construction shall be minimised by diverting runoff from the formation away from the batter until vegetation is established.

Scour Control**C211.14 MAINTENANCE AND INSPECTION**

1. The Contractor shall inspect all temporary erosion and sedimentation control works after each rain period and during periods of prolonged rainfall. Any defects revealed by such inspections shall be rectified immediately and these works shall be cleaned, repaired and augmented as required, to ensure effective erosion and sedimentation control thereafter.

***Contractor's
Responsibility***

2. The Contractor shall provide and maintain access from within the road reserve or from other locations acceptable to the Superintendent, for cleaning out sedimentation control works.

Access

C211.15 REMOVAL

1. All temporary erosion and sedimentation control works shall be removed by the Contractor when revegetation is established on formerly exposed areas before the end of the Contract. All materials used for the temporary erosion and sedimentation control works shall be removed from the site or otherwise disposed by the Contractor to the satisfaction of the Superintendent.

***Contractor's
Responsibility***

SPECIAL REQUIREMENTS

C211.16 RESERVED

C211.17 RESERVED

C211.18 RESERVED

C211.19 RESERVED

C211.20 RESERVED

SPECIFICATION C211 - CONTROL OF EROSION AND SEDIMENTATION

CLAUSE	CONTENTS	PAGE
GENERAL		1
C211.01	SCOPE	1
C211.02	REFERENCE DOCUMENTS	1
C211.03	EROSION AND SEDIMENTATION CONTROL PLAN	1
C211.04	EROSION AND SEDIMENTATION CONTROL MEASURES	2
PERMANENT EROSION AND SEDIMENTATION CONTROL		3
C211.05	EARTHWORKS FOR PERMANENT EROSION AND SEDIMENTATION CONTROL BASINS	3
C211.06	INLETS, SPILLWAYS AND LOW FLOW OUTLETS FOR SEDIMENTATION CONTROL BASINS AND SEDIMENT TRAPS	3
C211.07	DROP INLET SEDIMENT CONTROL.....	4
C211.08	CLEANING SEDIMENTATION CONTROL STRUCTURES.....	4
C211.09	RESERVED	4
TEMPORARY EROSION AND SEDIMENTATION CONTROL		4
C211.10	GENERAL.....	4
C211.11	TEMPORARY DRAINS	5
C211.12	TEMPORARY SEDIMENT TRAPS	5
C211.13	BATTER PROTECTION.....	5
C211.14	MAINTENANCE AND INSPECTION.....	5
C211.15	REMOVAL	6
SPECIAL REQUIREMENTS		6
C211.16	RESERVED	6
C211.17	RESERVED	6
C211.18	RESERVED	6
C211.19	RESERVED	6

C211.20 RESERVED 6

